



**DESIGN AND CONSTRUCTION  
OF THE ST. ANTHONY FALLS BRIDGE (I-35W)  
TOM DEHAVEN - FIGG**

# **I-35W COLLAPSE AUGUST 01, 2007**

---



## **NEW BRIDGE NEEDED QUICKLY**

---

**141,000 CARS A DAY USED  
THE BRIDGE  
ONE OF THE BUSIEST BRIDGES  
IN  
MINNESOTA**

**•CLOSE TO MAJOR TRAFFIC  
AREAS  
U OF M  
DOWNTOWN MINNEAPOLIS**

**•\$400K A DAY IN ROAD  
USERS COSTS**

# DESIGN BUILD ON ACCELERATED SCHEDULE





## **OWNER**

Minnesota Department of Transportation

**FLATIRON**  **MANSON**

## **CONTRACTOR**

Flatiron Constructors, Inc.

Manson Construction Co. – Johnson Bros.



## **DESIGNERS**

FIGG Bridge Engineers • TKDA • Oslund and Associates •  
Braun Intertec Corp.

# DESIGN BUILD PROPOSAL

---

August 8 - FMJV/FIGG shortlisted

August 23 Final RFP

September 14 – Technical Proposals submitted

37 Days





# WHAT HAPPENED IN THOSE 37 DAYS

---

Weekly Meetings between MnDOT  
and each short-listed Team

Confidential

Developed a Relationship

Increased Contractor's  
Comfort





# NEW ST. ANTHONY FALLS BRIDGE

---

## GOALS

- Safety
- Quality
- Aesthetics
- Public Relations
- Enhancements
- Environmental Compliance
- Time and Budget

# WHAT HAPPENED IN THOSE 37 DAYS

---

FMJV/FIGG Team deciding on Bridge type and erection method

Steel and Concrete alternates priced

Availability of Materials

Erection Plans developed



# **WHAT HAPPENED IN THOSE 37 DAYS**

---

FMJV/FIGG Team selected Concrete Bridge with both CIP and precast elements

Concrete was available and allowed FMJV to control their own destiny

Allowed exceeding 100 yr design life with HPC

Availability of Materials and labor was good

Erection Plans incorporated ideas from FIGG and FMJV

# WHAT HAPPENED IN THOSE 37 DAYS

---

FMJV/FIGG Team concerns

No Local Labor Agreement

Weather

Unknowns from Site

# DESIGN AND CONSTRUCTION CHALLENGES

---

## Get Foundations Started ASAP


- Required Preliminary Superstructure Design

## Cold Weather Protection

- Heating and Housing

## Site Geometric Constraints

- Contaminated Soils
- In-place Storm Sewers and Utilities
- Historic Wall




# DESIGN AND CONSTRUCTION CHALLENGES

## Drilled Shaft

- Upper layer of soft sandstone
- Artesian Conditions
- Load Test Required
- No piers in river

## Design for future LRT addition

- Added a week before RFP released
- Developed Criteria for LRFD Methodology




# BRIDGE DESCRIPTION

---

Bridge reflects series of modern arch forms – Elegant simplicity

Four-span bridge approximately 1,218' long

504' main span over Mississippi River





## **MNDOT'S ACTIONS LED TO PROJECT SUCCESS**

Delivered on all commitments they made

Shared their DB expertise

Staffed project with highly experienced, decisive staff

Encouraged OTS reviews

Reviewed all submittals within 7 days and averaged 2 days

## **MNDOT'S ACTIONS LED TO PROJECT SUCCESS**

Made Quality Manual a living document that was improved as the project progressed

Instituted “Hold Points” in QA/QC activities to assure Quality

Involved all stakeholders and got their input while eliminating all “red tape”. No voice was discounted.

# **FHWA'S ACTIONS LED TO PROJECT SUCCESS**

Full-time Bridge Engineer- Romeo Garcia

Gathered expertise from national experts on any issue

Brought in experts to share ideas from past DB projects

- Silica Fume
- Health Monitoring
- Quality Programs
- Drilled Shafts

# **OTHER ACTIONS LED TO PROJECT SUCCESS**

Labor Agreement with the Building trades

Efficient Labor force

Unaffected by cold weather

Selecting Cemstone to supply concrete mixes, expertise and concrete

**“Amazing! We just met with a concrete supplier who can actually provide answers and not just excuses” –**  
J. Barton- FMJV Superintendent

# LONG-TERM DURABILITY AND CORROSION PROTECTION

Develop design features to ensure superior durability

Exceed requirements of successful and proven Mn/DOT bridge standards

Ultimate goal: 100 year service life (Mn/DOT standard is 75 years)







# HIGH PERFORMANCE CONCRETE

---

Mix designs are tailored for each project element

The bridge superstructure, deck, footings, and drilled shafts all use concrete mixes with compressive strengths higher than required by design

# HIGH PERFORMANCE CONCRETE

---

Superior Compressive  
Strength

Low Permeability

High Freeze-thaw Resistance

Good Workability



# HIGH PERFORMANCE CONCRETE


---

Life 365 was used to estimate  
the time to corrosion

Developed by ACI Committee 365

Estimates for the mixes are:

Drilled Shafts	– 118 years
Footings	– 131 years
Piers	– 119 years
Substructure	– 115 years
Superstructure	– 171 years





# HIGH PERFORMANCE CONCRETE

---



All mixes include additives - silica fume and fly ash to reduce permeability and thermal cracking

Estimated chloride permeability is low - averaging 750 coulombs at 28 days. **Actual Measured was an average of 250 coulombs.**

Low shrinkage property of less than 0.021% - decreasing the potential penetration of contaminants


# BRIDGE DESCRIPTION

Variable depth superstructure

- 25' over piers
- 11' span 1 and 3 ends and midspan
- 6' span 4 midspan

Concrete piers supported by footings / drilled shafts socketed into rock

Expansion taken at abutment 1 and pier 4 (integral deck at abutment 5)







# MINI CASE STUDY – DRILLED SHAFTS



## MAIN PIER FOOTINGS

Span extensive storm drains  
Some locations straddle existing foundations





## MAIN PIER FOUNDATIONS

7' and 8' diameter drilled shafts  
100' long with socket into bedrock  
Slurry method with SC concrete

# **DRILLED SHAFT ISSUES**

- **REQUIRED LOAD TEST IN RELATIVELY UNKNOWN MATERIAL**
- **CRITICAL PATH ITEM**
- **FIRST DRILLED TEST HOLE FOUND ARTESIAN CONDITION**
- **LED TO MAJOR MEETING WITH ALL PARTIES TO DECIDE HOW TO PROCEED**
  - MNDOT, FHWA, OWNER'S EXPERTS, FMJV, BRAUN, CASE FOUNDATIONS, AND FIGG**
  - WILL A SHORTER SHAFT REACH CAPACITY?**

# DRILLED SHAFT ISSUES


- DRILLED SECOND TEST SHAFT ABOVE ARTESIAN
- USED 4 O-CELLS FOR SKIN FRICTION AND ONLY ONE TO ESTIMATE END BEARING
- USED SELF-CONSOLIDATION CONCRETE
- **TEST SHAFT EXCEEDED DESIGN BY 20%**
- **1<sup>ST</sup> PRODUCTION SHAFT AT CONTRACT DAY 50**





# STREAM LINED REVIEW

- **OTS REVIEW (OVER THE SHOULDER)**
- **HISTORIC WALL PROTRUDED OUT 20'. PIER 4 AND ENTIRE DESIGN AFFECTED**
- **SHARED INFORMATION WITH MNDOT AS SOLUTION WAS DEVELOPED.**
- **RESULT: IMPROVED SOLUTION AND STREAM LINED REVIEW**





# PROJECT ENHANCEMENTS

# MULTIPLE LEVELS OF REDUNDANCY

---

Two bridges, each with two box girders

Hundreds of high-strength steel strands embedded in each box girder

Pier under each box girder

Multiple drilled shaft foundations socketed into bedrock



# CORROSION PROTECTION STRATEGIES

---

Include corrosion resistant design details

Utilize high performance materials

Provide multiple layers of protection of key structural elements

Provide high quality construction







# POST-TENSIONED CONCRETE BRIDGE

---

Bi-directional prestressing of the concrete deck to reduce the potential for cracking

Minimum 250 psi residual compression in the longitudinal direction of the deck

Zero tension criteria in the transverse direction of the concrete deck under full load



# CORROSION RESISTANT DESIGN DETAILS

---

Integral Wearing Surface -  
monolithic application of  
additional concrete above what is  
required structurally

Additional concrete  
precompressed both directions  
with deck PT

4.5" clear cover to top deck  
reinforcing and prestressing

Top 0.5" reserved for deck milling  
and profiling




# REINFORCING AND PRESTRESSING STEEL

---

Epoxy coated reinforcing used at all locations, except drilled shafts

Prestressing steel is protected by the concrete, plastic or galvanized ducts and high performance grout

Hardware and other steel components that are embedded in the concrete are galvanized or epoxy coated





# CORROSION PROTECTION OF POST- TENSIONING STRAND SYSTEMS

---



High Performance Concrete provides a dense, barrier with low permeability

Post-tensioning ducts – corrugated plastic in the top slab, high-density polyethylene for external tendons, and galvanized steel corrugated duct for all other locations

Enhanced cementitious prepackaged grout with Thixotropic Properties

# HEALTH MONITORING "SMART BRIDGE" SYSTEMS

---

Integrated Bridge Sensor Monitoring System

Record of structural behavior (structure monitoring)


Control of the automated anti-icing system



# SENSORS FOR STRUCTURAL BEHAVIOR

---

- Vibrating Wire Strain Gauge with Temperature Reading
- Linear Potentiometer
- Accelerometer
- Chloride Penetration Sensor




Vibrating wire strain gauges, installed in select locations, will measure how the bridge is resisting loads and also the temperature of the concrete



# SENSORS FOR STRUCTURAL BEHAVIOR

---

- Vibrating Wire Strain Gauge with Temperature Reading
- Linear Potentiometer
- Accelerometer
- Chloride Penetration Sensor




Placed at expansion joints and bearings to measure bridge movements which can be compared to expected values



# SENSORS FOR STRUCTURAL BEHAVIOR

---

- Vibrating Wire Strain Gauge with Temperature Reading
- Linear Potentiometer
- Accelerometer
- Chloride Penetration Sensor



Accelerometers monitor bridge deflections under loads






# SENSORS FOR STRUCTURAL BEHAVIOR

---

- Vibrating Wire Strain Gauge with Temperature Reading
- Linear Potentiometer
- Accelerometer
- Chloride Penetration Sensor



Monitor levels of chlorides in the concrete deck to assist with maintenance activities





# PROJECT CONSTRUCTION





**GOAL:**  
**WORK EVERYWHERE POSSIBLE**  
**AT THE SAME TIME**



## **SUPERSTRUCTURE**

25' to 11' high CIP box girders (back spans)  
25' to 11' high precast segments (main span)  
Back spans and main span cast simultaneously





**SUPERSTRUCTURE  
(BACK SPANS ON FALSEWORK)**






**SUPERSTRUCTURE  
(MAIN SPAN — PRECAST SEGMENTS)  
(CASTING YARD — LONGLINE CASTING)**

All 8 headings cast simultaneously  
Longline casting method  
Heated enclosures





**SEGMENT LENGTHS - 13.5' TO 16.5'**  
**WEIGHTS - 380 KIPS TO 216 KIPS**  
**15 SEGMENTS PER CANTILEVER**

**SUPERSTRUCTURE**  
**(MAIN SPAN — PRECAST SEGMENTS)**  
**(UNIDIRECTIONAL CANTILEVER)**





**SPANS 1 AND 3**

CIP casting complete  
Longitudinal span PT stressing complete  
Currently supported on falsework





**SPAN 2  
(PRECAST MAIN SPAN)**

**PRECASTING IS COMPLETE  
120 PRECAST SEGMENTS WERE PLACED  
IN 47 DAYS  
PLACED UP TO 6 PER DAY**





**SPAN 2**

Precast Segment Erection





**SPAN 2**

Cantilever Erection

- **MONUMENTS  
AT BRIDGE  
ENDS**



- **MONUMENTS WITH  
AESTHETIC LIGHTING**





# I-35W PROGRESS

## Project Milestones

*Taking on the many challenges of building the new I-35W Bridge on an accelerated schedule has provided an opportunity to show the world—because the world was watching—how a city can triumph over tragedy.*

— Peter F. Sanderson, Flatiron-Marston  
Project Manager

Design Started 10/8/07

Construction Started



Community design charrette



First Sidewalk Superintendent Talk conducted by Peter Sanderson



First drilled shaft installed; reinforcing is shown being prepared for the shafts



Test shaft drilled



Last drilled shaft installed

# I-35W PROGRESS



→ First footing poured



→ Falsework construction began



→ Coldest day:  
Low -14 Wind chill -36

→ First pier form removed



1/15

92

22/-5°

1/23

100

3/-9°

1/28

105

43/24°

1/30

107

-2/-14°

2/10

118

-4/-14°

2/23

131

32/11°

2/25

151

37/22°

→ First pier poured



→ First segment, or box girder, cast



→ Last footing poured





# I-35W PROGRESS



DATE	3/14/08	4/2
DAYS	151	170
TEMP	40/27°F	43/24°



5/1	5/7	5/25	5/31	6/6
198	206	223	229	236
68/47°	66/49°	84/61°	79/66°	75/64°



# I-35W PROGRESS



→ Roadway concrete paving began



→ Last box girder segment erected



→ Northbound bridge cantilevers connected

6/16

245

73/52°

6/30

259

83/59°

7/10

269

85/63°

7/16

275

85/63°

7/24

283

84/68°

8/1

291

87/68°

Actual Opening 9/15  
Day 336

Original Completion  
Date; design and build  
in fifteen months

Dedication & opening  
(eleven months)

→ Bridge coating in "Snowbound" white began



→ Southbound bridge cantilevers connected



→ Construction stopped at 3:00 p.m. for six hours in remembrance of August 1, 2007; 6:05 p.m.





# I-35W PROGRESS



5-5-08



Creating  
Bridges as Art



6-18-08

# I-35W PROGRESS

*(C) Actos Aerial Images*



**5-5-08**



**7-14-08**



# I-35W PROGRESS



May 2008



Open to Traffic Sept 2008

# **I-35W PROGRESS**

## **OPEN TO TRAFFIC SEPTEMBER 15,**







# NEW ST. ANTHONY FALLS BRIDGE

---

## GOALS

- SAFETY

**NO LOST TIME ACCIDENTS**

- QUALITY

**DETAILED QC IN DESIGN AND  
CONSTRUCTION**

- AESTHETICS

**AWARD WINNING**

- PUBLIC RELATIONS

**EXCEPTIONAL IN ALL ASPECTS**

- ENHANCEMENTS

**ELIMINATED ROADWAY  
EXCEPTIONS, HP CONCRETE,  
SMART BRIDGE, LED LIGHTS, ETC**

- ENVIRONMENTAL COMPLIANCE

**THROUGHOUT CONSTRUCTION**

- TIME AND BUDGET

**ABOUT 3 MONTHS EARLY AND  
NO EXTRA COST**

# **FIGG RECOMMENDATIONS FOR DB PROJECTS**

---

- **MANDATE WEEKLY MEETINGS DURING RFP PROCESS**
- **MANDATE OTS REVIEWS AND COMPEL OWNER/DESIGNER INTERACTION**
- **ELIMINATE “RED TAPE” DELAYS  
ALL AGENCIES SHOULD BE AS RESPONSIVE AS THEY WERE ON I35W**
- **ENCOURAGE INNOVATION- HPC, SILICA FUME MIXES, LED LIGHTING, ETC**





# I35W ST. ANTHONY FALLS BRIDGE SUCCESS

**TEAM EFFORT**

**MNDOT AND FHWA  
PROFESSIONALISM**

**LOCAL UNION LABOR**

**ACHIEVED HIGH  
QUALITY AND SAFETY  
WITH AN ACCELERATED  
SCHEDULE**






# SPECIAL RECOGNITION AND THANKS

---

- TKDA
- BRAUN-INTERTEC
- AETOS AERIAL IMAGES





# I35W ST. ANTHONY FALLS BRIDGE QUESTIONS

